
GPIP Vessel Haulout Project Subject Matter Expert Mtg No. 1June 1, 2023



Garry White GPIP Director



Michael Harmon, P.E.
CBS Municipal Eng & PM



Dick Somerville, P.E., PIC
Tyler Bradshaw, P.E., PM
Greg Meissner – Marine Services Planner

Introductions Subject Matter Expert (SME) Panel

- 1. Mike Johnson
- 2. Rob Lihou
- 3. Eric Majeski
- 4. Jeremy Serka
- 5. Greg Meissner

Thanks to You All for Participating!

Presentation Agenda

- Project Charter Goals & Schedule
- General Scope of Improvements
- Meetings Schedule
- Review Concept Plan Options & Recommend a Preferred Alternative – Today's Primary Focus
- Next Steps

Project Charter - Goals

- Develop 150 T haulout facility having capacity to haul the majority of the Sitka fleet
- 2. Plan future infrastructure to haul vessels greater than 150 T
- Plan future infrastructure via GPIP Access Ramp to haul vessels & barges for repair and refurbishment (Modified by GPIP BOD on 4.26.23 during site selection for the haulout pier)
- 4. Develop GPIP uplands into a working shipyard to support the marine services industry
- 5. Retain and grow local marine service sector jobs
- 6. Provide critical infrastructure for emergency vessel repairs
- 7. Reduce travel costs and emissions for vessels having to travel to other regional shipyards

Project Charter – Cover Sheet

| Project Status: (highlight green, yellow, red) | | | |
|---|---|--|--|
| General | Schedule | Budget | |
| Milestones: | | | |
| Recently Completed | | Upcoming | |
| ✓ Project Charter Developed with Risk Scori GPIP Board of Directors Review Nov 21, 2 ✓ Contract Phase IA of Project: Planning, Environmental, Prelim Engr, Preferred Operation ✓ Site Selection | Investigations Design tion Phase IB – Is Preliminary D | Phase IA – Planning and Project Management, Site Investigations, Environmental Permitting, Preliminary Design Phase IB – Issue CMAR RFP for Preferred Option & Preliminary Design | |
| Project Budget: | | | |
| Estimated Total Project Cost | | \$12,000,000 | |
| Working Capital | | \$8,180,000 | |
| Loans | | \$0.00 | |
| Grants | | \$0.00 | |
| Other | | \$0.00 | |
| Total Funded | | \$8,180,000 | |
| Funding Gap | | \$3,820,000 | |
| Encumbrances to Date | | \$0.00 | |
| Unencumbered Funds | | \$8,180,000 | |
| Contract Management: (list all contracts anticipated | d on the project) | | |
| Contractor/Function* | Type** | ** <u>Amount</u> % Of Project | |
| PM, Planning, Surveying, PIP, Concept | s, Costs, T&M | | |

| Contract Management: (list all contracts anticipated on the project) | , | | |
|---|--------------------------------|---------------------|---------------------------------|
| Contractor/Function* PM, Planning, Surveying, PIP, Concepts, Costs, Preferred Alternative & Basis of Design, | Type** <mark>T&M</mark> | Amount \$365,000 | % Of Project <mark>5%</mark> |
| Environmental PM, Geotech, Final Design, CMAR RFP, CM Services CA/CI | T&M/LS | \$585,000 | <mark>7%</mark> |
| CMAR Contractor | CMAR | \$6,000,000 | <mark>73%</mark> |
| Travel Lift Purchase | LS | \$1,230,000 | <mark>15%</mark> |
| I . | | | |

Project Design & Construction Schedule

| Task Description | Begin | Complete |
|---|----------|-----------|
| 1. Project Charter Approval by GPIP BOD | | 11.21.22 |
| 2. Select & Contract PM/Port Planner/Engineer | 12.12.22 | 3.29.23 |
| 3. Planning, surveying, PIP, Concepts, Costs, Final Charter | 4.3.23 | 7.31.23 |
| 4. Geotech Permits, Field Investigation & Report | 5.22.23 | *10.31.23 |
| 5. Environmental Studies and Regulatory Permits | 5.22.23 | *6.30.24 |
| 6. Prelim. (35%) Design, CMAR Solicitation & Selection | 8.1.23 | 1.31.24 |
| 7. Final Design (PND & CMAR) | 2.1.24 | 7.1.24 |
| 8. Material Procurement | 4.1.24 | 10.1.24 |
| 9. On Site Construction | 8.1.24 | 12.31.24 |

General Scope of Improvements

- 1. Maximize Phase 1 infrastructure development within initial \$8.2 M Phase 1 budget
- 2. Procure a 150 Ton Marine Boat Hoist
- 3. Construct Haulout Pier for 150T hoist with ability to expand to a larger capacity in the future
- 4. Wash down pad(s) & wash water treatment
- 5. Boatyard maximize secured space on site for both work & storage operations
- 6. Storm water runoff with discharge treatment from boat yard meeting regulatory requirements
- 7. Power, lighting, water and sewer services
- 8. On site restroom, small shop and office space

Note: It is not anticipated that all improvements will be possible within the initial budget so scope decisions will need to be made during design development.

Wrangell 150T Travelift Boat Hoist



Wrangell 300 T ASCOM Boat Hoist



Hoonah 200T Travelift, Haulout Pier, Wash Down & Boatyard



Boatyard Transporters (35-100T)







Heated Wash Down Pad (Hoonah Boat Yard)



Washwater Treatment, Restrooms & Small Shop Building (Hoonah Boat Yard)



Boat Yard Utilities – fire, water, sewer, power, lighting & security









Boat Yard: Stormwater Yard Runoff Controls Water Quality Unit – Collection & Treatment




Meetings Schedule

- 1. Complete: GPIP BOD Mtg No. 1 Haulout Pier Site No. 2 Selected
- Today: Subject Matter Experts (SME) Mtg 1 present concept designs & costs, receive comments, suggestions & haulout pier conceptual preference
- 3. June 22: GPIP BOD Mtg No. 2 present & adopt preferred concept plan based on SME 1 comments
- 4. July 6 (TBD): SME Mtg No. 2 present final Charter w/ preferred concept plan, budget & Basis of Design
- 5. July 20 (TBD): GPIP BOD Mtg No. 3 Approval of final Charter and refined Basis of Design
- 6. July 25: Assembly presentation & approval of Preferred Plan and Final Charter


GPIP VHO – Existing Conditions Site Plan




Vessel Haulout Pier Concept 1 - 150T Pier Only




Vessel Haulout Pier Concept 2 - 150T Pier & Future 300T Pier



Vessel Haulout Pier Concept 3 - 150T Pier & Future 300T Pier



Vessel Haulout Pier Concept 4 - 150T Pier & Future 300T Pier



Vessel Haulout Pier Boatyard Concept 1 & WDP Options



Rough Order Magnitude (ROM) Budget Concept No. 1 Haulout Pier

| Item | Cost (\$K) | \$ Summation |
|---|------------|-----------------|
| 1. General Contract Requirements (Base) | \$603 | |
| 2. 150T Haulout Pier | \$2,854 | |
| 3. Uplands Expansion at Pier | \$945 | |
| 4. North Boat Yard Site Grading (no utilities) | \$1,105 | |
| 5. Wash Down Pad & Treatment Facilities | \$575 | |
| 6. Contingency & Indirect Costs (35%) | \$2,128 | <u>\$8,210</u> |
| 7. General Contract Requirements (Options) | \$362 | |
| 8. 150T Boat Hoist | \$1,350 | |
| 9. 40T Yard Transporter | \$250 | |
| 10. Deckover, 32x60 | \$742 | |
| 11. Queuing Float, Deck & Gangway | \$456 | |
| 12. Utility Building, 24x40 | \$770 | |
| 13. Contingency & Indirect Costs (35%) | \$1,375 | <u>\$5,305</u> |
| Total Base + All Options | | <u>\$13,515</u> |
| Excludes West Boat Yard, Road, Utilities, Paving & Security | | |

Rough Order Magnitude (ROM) Budget Concept No. 2 Haulout Pier

| Item | Cost (\$K) | \$ Summation |
|---|------------|-----------------|
| 1. General Contract Requirements (Base) | \$651 | |
| 2. 150T Haulout Pier | \$3,249 | |
| 3. Uplands Expansion at Pier | \$1,033 | |
| 4. North Boat Yard Site Grading (no utilities) | \$1,105 | |
| 5. Wash Down Pad & Treatment Facilities | \$575 | |
| 6. Contingency & Indirect Costs (35%) | \$2,314 | <u>\$8,926</u> |
| 7. General Contract Requirements (Options) | \$747 | |
| 8. 150T Boat Hoist | \$1,350 | |
| 9. 40T Yard Transporter | \$250 | |
| 10. 150T Deckover, 32x60 | \$742 | |
| 11. 300T Haulout Pier | \$2,501 | |
| 12. 300T Deckover, 40x100 | \$1,344 | |
| 13. Queuing Float, Deck & Gangway | \$456 | |
| 14. Utility Building, 24x40 | \$770 | |
| 15. Contingency & Indirect Costs (35%) | \$2,856 | <u>\$11,014</u> |
| Total Base + All Options | | <u>\$19,941</u> |
| Excludes 300T Boat Hoist, West Yard, Road, Utilities, Paving & Security | | |

Rough Order Magnitude (ROM) Budget Concept No. 3 Haulout Pier

| Item | Cost (\$K) | \$ Summation |
|---|------------|-----------------|
| 1. General Contract Requirements (Base) | \$711 | |
| 2. 150T Haulout Pier | \$3,852 | |
| 3. Uplands Expansion at Pier | \$1,033 | |
| 4. North Boat Yard Site Grading (no utilities) | \$1,105 | |
| 5. Wash Down Pad & Treatment Facilities | \$575 | |
| 6. Contingency & Indirect Costs (35%) | \$2,548 | <u>\$9,822</u> |
| 7. General Contract Requirements (Options) | \$669 | |
| 8. 150T Boat Hoist | \$1,350 | |
| 9. 40T Yard Transporter | \$250 | |
| 10. Deckover, 32x100 | \$1,124 | |
| 11. 300T Haulout Pier | \$1,824 | |
| 12. 300T Deckover, 40x600 | \$862 | |
| 13. Queuing Float, Deck & Gangway | \$456 | |
| 14. Utility Building, 24x40 | \$770 | |
| 15. Contingency & Indirect Costs (35%) | \$2,557 | <u>\$9,861</u> |
| Total Base + All Options | | <u>\$19,683</u> |
| Excludes 300T Boat Hoist, West Yard, Road, Utilities, Paving & Security | | |

Rough Order Magnitude (ROM) Budget Concept No. 4 Haulout Pier

| Item | Cost (\$K) | \$ Summation |
|---|------------|-----------------|
| 1. General Contract Requirements (Base) | \$651 | |
| 2. 150T Haulout Pier | \$3,333 | |
| 3. Uplands Expansion at Pier | \$945 | |
| 4. North Boat Yard Site Grading (no utilities) | \$1,105 | |
| 5. Wash Down Pad & Treatment Facilities | \$575 | |
| 6. Contingency & Indirect Costs (35%) | \$2,313 | <u>\$8,921</u> |
| 7. General Contract Requirements (Options) | \$525 | |
| 8. 150T Boat Hoist | \$1,350 | |
| 9. 40T Yard Transporter | \$250 | |
| 10. Deckover, 32x60 | \$742 | |
| 11. 300T Haulout Pier | \$1,632 | |
| 12. Queuing Float, Deck & Gangway | \$456 | |
| 13. Utility Building, 24x40 | \$770 | |
| 14. Contingency & Indirect Costs (35%) | \$2,004 | <u>\$7,729</u> |
| Total Base + All Options | | <u>\$16,650</u> |
| Excludes 300T Boat Hoist, West Yard, Road, Utilities, Paving & Security | | |

Next Steps

- Debrief with CBS on Today's Meeting
- Update Preferred Alternative Concept & ROM Budget Estimate
- Prepare Geotech Investigation Permit Application
- June 22 Meet with GPIP BOD No. 2
- July 6 (TBD) Meet with SME No. 2

GPIP Vessel Haulout Project SME Work Session

Thank you for your questions, comments & suggestions!

Please submit comments by:

- Email: GPIPHaulOut@cityofsitka.org
- Comment Forms at the back of the room

Please visit our Project Page for updates:

https://www.citvofsitka.com/departments/PublicWorks/GPIPHaulOu

t







